




Quality Engineered Products

These products have been engineered and produced to the highest quality standards and meet or exceed applicable U.S. government standards including OSHA, ASME B30.20, B30.9 and B30.17. Proof-testing with certification is available upon request for a nominal charge. Custom devices can be designed to meet your lifting application needs (see end of Lifting Devices section).

Product Overview



Lifting Beams

Allow multiple pick points for balance and support. The top rigging adds stability to the lift. Available in nine standard styles.



Gantry Cranes

These portable cranes allow for the pick-up and transport of a load wherever you have a smooth and level floor. Available in either steel or aluminum and fixed or adjustable height.



Coil Lifters

Use to lift, manipulate and reposition coils. Requires minimum aisle space equal to lifter arm length. Available in two standard styles.




Forklift Accessories

Three styles of booms and two hook devices provide added lifting capabilities to your forklift trucks.



Beam/Girder Clamps

For use in lifting and positioning structural beams. Two styles may also be hung from load bearing beams to suspend hoists or other lifting devices.



Barrier Grabs

Scissor-style grab is the easy way to lift and move concrete road barriers. Auto-latch for hands-off operation.



Pipe Grab

For lifting and positioning of steel, iron and concrete pipes.




Manhole Sleeve Lifter

The quick and easy way to place cast manhole sleeves. 2-leg and 3-leg configurations available.

Lifting Device Return Policy

- Items to be returned **MUST BE UNUSED** and in like-new condition.
- Contact Lift-All's customer service department to obtain an RMA number; no returns will be accepted without it.
- The customer must prepay freight to the designated location.
- Request for return **MUST** be made within 30-days of the original shipment date (not receipt date).
- A restocking fee of 25% shall be charged for all authorized returns.
- Credit will be issued **after** receipt, inspection, and acceptance of the return.
- Custom (non-standard) items or modified items are non-returnable and non-refundable.

ADJUSTABLE SPREADER/LIFTING BEAM (ASLB16)




Features

- Use for 2, 3, or 4-point lifting, or as a spreader beam (optional top rigging).
- Adjustable lifting points.
- Handles both wide and unbalanced loads.
- Low headroom capability.
- Shackles included.
- 6" spread adjustments.
- 4" bail adjustments.

Options


- Pair of swivel hooks*.
- Top chain rigging available.



Rated Capacity (tons)	Part Number*	Spread (ft.)		Bail Adjustment (in.)	Bolt Style Anchor Shackles (tons)		Headroom (in.)	Weight (lbs.)
		Max.	Min.		Top	Bottom		
1/4	ASLB.5X4	4	1	16	1.50	1.50	8.00	45
1/2	ASLB1X4	4	1	16	1.50	1.50	8.00	45
1/2	ASLB1X6	6	3	24	1.50	1.50	10.00	80
1/2	ASLB1X8	8	4	32	1.50	1.50	11.00	135
1/2	ASLB1X10	10	5	40	1.50	1.50	11.00	145
1	ASLB2X6	6	3	24	1.50	1.50	11.00	100
1	ASLB2X8	8	4	32	1.50	1.50	12.00	140
1	ASLB2X10	10	5	40	1.50	1.50	12.00	175
2	ASLB4X6	6	3	24	3.25	2.00	14.00	130
2	ASLB4X8	8	4	32	3.25	2.00	15.00	200
2	ASLB4X10	10	5	40	3.25	2.00	16.00	280
4	ASLB8X8	8	4	32	4.75	4.75	18.00	290
4	ASLB8X10	10	5	40	4.75	4.75	20.00	420
4	ASLB8X12	12	6	48	4.75	4.75	20.00	500
5	ASLB10X8	8	4	32	6.50	4.75	20.00	320
5	ASLB10X10	10	5	40	6.50	4.75	21.00	465
5	ASLB10X12	12	6	48	6.50	4.75	21.00	550
7	ASLB14X12	12	6	48	8.50	6.50	25.00	790

* For optional swivel hooks, add an S to part number and contact Lift-All for pricing.

ADJUSTABLE LIFTING BEAM (ALB17)




Features

- Adjust bail horizontally for lifting unbalanced loads.
- Provides clearance in low headroom applications.
- Spread adjusts in 6" increments.
- Shackles included.

Options


- Pair of swivel hooks*.



Rated Capacity (tons)	Part Number*	Spread (ft.)		Bail Adjustment Increments (in.)	Bail Dimensions (in.)				Headroom (in.)	Bail Travel (Half of Center)	Shackle Size	Weight (lbs.)
		Max.	Min.		Height	Opening Width	Opening Height	Thickness				
1-1/4	ALB2.5X6	6	3	3	1	3	5	0.63	14.7	12	2	120
2	ALB4X6	6	3	3	1	3	5	0.63	14.7	12	2	140
4	ALB8X8	8	4.5	6	1	4	7	0.75	19.8	18	3.25	315
5	ALB10X10	10	5	6	1	4	7	1.00	22.4	18	4.75	440

* For optional swivel hooks, add an S to part number and contact Lift-All for pricing.


FIXED SPREAD LIFTING BEAM (FSLB19)



Rated Capacity (tons)	Part Number	Spread (ft.)	Bail Dimensions A • B • C • H (in.)	Headroom (in.)	Weight (lbs.)
1/2	FSLB1X2	2	A • 0.75 B • 3.00 C • 5.00 H • 0.89	13.75	20
	FSLB1X3	3		13.75	26
	FSLB1X4	4		13.75	33
	FSLB1X6	6		13.75	48
	FSLB1X8	8		14.75	75
	FSLB1X10	10		14.75	93
1	FSLB2X2	2	A • 1.00 B • 3.00 C • 5.00 H • 0.89	14.75	26
	FSLB2X3	3		14.75	35
	FSLB2X4	4		14.75	44
	FSLB2X6	6		15.75	72
	FSLB2X8	8		15.75	93
	FSLB2X10	10		16.75	131
2	FSLB4X3	3	A • 1.00 B • 3.00 C • 5.00 H • 1.00	16.75	45
	FSLB4X4	4		17.75	55
	FSLB4X6	6		19.75	108
	FSLB4X8	8		19.75	140
	FSLB4X10	10		19.75	188
3	FSLB6X3	3	A • 1.50 B • 4.00 C • 7.00 H • 1.00	18.50	58
	FSLB6X4	4		20.50	87
	FSLB6X6	6		20.50	118
	FSLB6X8	8		20.50	222
	FSLB6X10	10		20.50	272

Features

- Fixed spread.
- Eye hooks with latches.
- Sealed construction for cleaner beam.





BASKET SLING LIFTING BEAM (BSLB18)




Features

- Best beam for low headroom applications.
- Fixed spread.
- Bent bar hooks allow for 2" wide sling eyes:
 - One set for 3' and 4' spreads.
 - Two sets for 6' through 12' spreads.
- Spread 2 is one-half of spread 1.



Rated Capacity (tons)	Part Number	Spread (ft.)	Bail Dimensions A • B • C • T (in.)	Headroom (in.)	Weight (lbs.)
1/2	BSLB1X3	3		8.50	40
	BSLB1X4	4	A • 0.88	8.50	48
	BSLB1X6	6	B • 3.00	8.50	78
	BSLB1X8	8	C • 5.00	8.50	95
	BSLB1X10	10	T • 0.75	8.50	113
	BSLB1X12	12		9.50	171
1	BSLB2X3	3		8.50	40
	BSLB2X4	4	A • 0.88	8.50	48
	BSLB2X6	6	B • 3.00	9.50	93
	BSLB2X8	8	C • 5.00	10.50	136
	BSLB2X10	10	T • 0.75	10.50	175
	BSLB2X12	12		11.50	239
2	BSLB4X3	3		9.50	52
	BSLB4X4	4	A • 0.88	10.50	75
	BSLB4X6	6	B • 3.00	10.50	139
	BSLB4X8	8	C • 5.00	11.50	169
	BSLB4X10	10	T • 0.75	12.50	246
	BSLB4X12	12		13.50	326
5	BSLB10X3	3		13.50	104
	BSLB10X4	4	A • 2.00	14.50	135
	BSLB10X6	6	B • 4.00	15.50	211
	BSLB10X8	8	C • 7.00	16.50	310
	BSLB10X10	10	T • 1.25	17.50	423
	BSLB10X12	12		19.50	618

LOW HEADROOM MULTIPLE SPREAD LIFTING BEAM (LHLB20)



Features



- Great for low headroom applications.
- Swivel hooks with latches are standard.
- 3' & 4' beams have two spreads.
- Beams 6' and longer have three spreads.
- Inner spread lengths are shorter than outer spreads by 1' increments.
- Additional or custom hole configuration available.

Rated Capacity (tons)	Part Number	Spread (ft.)	Bail Dimensions (in.)				Hook Opening	Headroom (in.)	Weight (lbs.)
			Bail Height	Opening Width	Opening Height	Thickness			
1/2	LHLB1X3	3	0.88	3	5	0.75	0.91	13	40
	LHLB1X4	4					0.91	13	50
	LHLB1X6	6					0.91	13	65
	LHLB1X8	8					0.91	13	80
	LHLB1X10	10					0.91	14	125
	LHLB1X12	12					0.91	14	145
	LHLB1X14	14					0.91	15	210
	LHLB1X16	16					0.91	16	360
	LHLB1X18	18					0.91	18	465
	LHLB1X20	20					0.91	20	490
	LHLB1X24	24					0.91	24	765
	LHLB1X30	30					0.91	30	1280
1	LHLB2X3	3	0.88	3	5	0.75	0.91	13	40
	LHLB2X4	4					0.91	13	50
	LHLB2X6	6					0.91	14	80
	LHLB2X8	8					0.91	14	105
	LHLB2X10	10					0.91	15	150
	LHLB2X12	12					0.91	16	275
	LHLB2X14	14					0.91	17	365
	LHLB2X16	16					0.91	18	390
	LHLB2X18	18					0.91	19	505
	LHLB2X20	20					0.91	20	640
	LHLB2X24	24					0.91	22	1025
2	LHLB4X3	3	0.88	3	5	0.75	0.91	13	40
	LHLB4X4	4					0.91	14	60
	LHLB4X6	6					0.91	15	95
	LHLB4X8	8					0.91	16	150
	LHLB4X10	10					0.91	17	265
	LHLB4X12	12					0.91	18	295
	LHLB4X14	14					0.91	19	400
	LHLB4X16	16					1.00	22	690
	LHLB4X18	18					1.00	22	775
	LHLB4X20	20					1.00	22	860
	LHLB4X24	24					1.00	22	1665

Industrial Lifting Beams


LOW HEADROOM MULTIPLE SPREAD LIFTING BEAM (LHLB20)

Options:



Rated Capacity (tons)	Part Number	Spread (ft.)	Bail Dimensions (in.)				Hook Opening	Headroom (in.)	Weight (lbs.)
			Height	Opening Width	Opening Height	Thickness			
3	LHLB6X3	3	1.25	3	5	1	1	14	55
	LHLB6X4	4					1	15	80
	LHLB6X6	6					1	16	155
	LHLB6X8	8					1	17	225
	LHLB6X10	10					1	18	260
	LHLB6X12	12					1	20	400
	LHLB6X14	14					1	22	620
	LHLB6X16	16					1	22	705
	LHLB6X18	18					1.36	26	1280
	LHLB6X20	20					1.36	26	1420
	LHLB6X24	24					1.36	26	1690
5	LHLB10X3	3	2	4	7	1.25	1.36	18	100
	LHLB10X4	4					1.36	19	145
	LHLB10X6	6					1.36	20	210
	LHLB10X8	8					1.36	22	280
	LHLB10X10	10					1.36	24	380
	LHLB10X12	12					1.36	25	570
	LHLB10X14	14					1.61	30	1045
	LHLB10X16	16					1.61	30	1185
	LHLB10X18	18					1.61	30	1325
	LHLB10X20	20					1.61	30	1470
	LHLB10X24	24					1.61	33	2320
7-1/2	LHLB15X3	3	2	4	7	1.25	1.61	21	130
	LHLB15X4	4						22	170
	LHLB15X6	6						24	235
	LHLB15X8	8						25	320
	LHLB15X10	10						27	495
	LHLB15X12	12						30	900
	LHLB15X14	14						30	1050
	LHLB15X16	16						30	1190
10	LHLB20X3	3	2.5	5	9	1.50	2.08	22	145
	LHLB20X4	4						23	165
	LHLB20X6	6						25	260
	LHLB20X8	8						27	410
	LHLB20X10	10						30	770
	LHLB20X12	12						30	910
	LHLB20X14	14						30	1055
	LHLB20X16	16						33	1475
	LHLB20X18	18						33	1985

HEAVY DUTY TWIN BASKET SLING LIFTING BEAM (HDLB22)




Features

- For use with slings in a basket hitch.
- Latch hooks designed to minimize sling eye damage.
- One set of fixed hooks standard for 3' and 4' lengths (total of 4-hooks).
- Two sets of fixed hooks standard for all lengths over 4' (total of 8-hooks).
- Inner spread is one-half of outer spread.
- Extra spreads available upon request.




Rated Capacity (tons)	Part Number	Spread (ft.)	Bail Dimensions (in.)				Hook Opening	Headroom (in.)	Weight (lbs.)
			Height	Opening Width	Opening Height	Thickness			
1/2	HDLB1X3	3	0.88	3	5	0.75	1.06	9	53
	HDLB1X4	4						9	68
	HDLB1X6	6						9	116
	HDLB1X8	8						9	158
	HDLB1X10	10						10	210
	HDLB1X12	12						10	231
1	HDLB2X3	3	0.88	3	5	0.75	1.13	9	53
	HDLB2X4	4						9	68
	HDLB2X6	6						10	152
	HDLB2X8	8						11	221
	HDLB2X10	10						11	242
	HDLB2X12	12						12	305
2	HDLB4X3	3	0.88	3	5	0.75	1.13	10	74
	HDLB4X4	4						11	95
	HDLB4X6	6						11	168
	HDLB4X8	8						12	236
	HDLB4X10	10						13	315
	HDLB4X12	12						14	394
5	HDLB10X3	3	2	4	7	1	1.13	14	95
	HDLB10X4	4						15	168
	HDLB10X6	6						16	289
	HDLB10X8	8						17	368
	HDLB10X10	10						23	473
	HDLB10X12	12						23	525
7-1/2	HDLB15X3	3	2	4	7	1.25	1.75	15	158
	HDLB15X4	4						16	189
	HDLB15X6	6						17	336
	HDLB15X8	8						18	431
	HDLB15X10	10						18	525
	HDLB15X12	12						20	735
10	HDLB20X3	3	2	4	7	1.25	1.75	16	163
	HDLB20X4	4						17	210
	HDLB20X6	6						18	347
	HDLB20X8	8						20	525
	HDLB20X10	10						23	893
	HDLB20X12	12						23	1050

TWIN HOIST LIFTING BEAM (THLB25)



Features

- Use two (or more) hoists to increase lifting stability.
- Swivel hook with latch standard.
- Multiple options available.







Rated Capacity (tons)	Part Number	Spread (ft.)	Bail Dimensions (in.)				Hook Opening	Headroom (in.)	Weight (lbs.)
			Height	Opening Width	Opening Height	Thickness			
2	THLB4X6	6	1.5	3	5	0.63	1.09	17	125
	THLB4X8	8						17	160
	THLB4X10	10						18	240
	THLB4X12	12						18	280
	THLB4X14	14						19	360
	THLB4X16	16						19	400
4	THLB8X6	6	1.5	3	5	0.63	1.61	20	160
	THLB8X8	8						21	240
	THLB8X10	10						22	310
	THLB8X12	12						23	410
	THLB8X14	14						23	500
	THLB8X16	16						25	725
6	THLB12X6	6	1.5	3	5	0.75	2.08	28	220
	THLB12X8	8						29	300
	THLB12X10	10						29	380
	THLB12X12	12						31	550
	THLB12X14	14						31	640
	THLB12X16	16						31	780
10	THLB20X6	6	2	4	7	1	2.27	29	340
	THLB20X8	8						29	420
	THLB20X10	10						32	800
	THLB20X12	12						32	920
	THLB20X14	14						32	1100
	THLB20X16	16						32	1220
15	THLB30X8	8	2	4	7	1.25	3.02	38	814
	THLB30X10	10						38	952
	THLB30X12	12						38	1155
	THLB30X14	14						41	2123
	THLB30X16	16						41	2374
20	THLB40X8	8	2	4	7	1.25	3.02	36	913
	THLB40X10	10						39	1243
	THLB40X12	12						39	1393
	THLB40X14	14						39	2119
	THLB40X16	16						39	2416

FIXED SPREADER BEAM (FSB30)

Features

- Ideal where headroom is not limited.
- Adds stability to lift.
- Chain rigging standard.
- Wire rope rigging is available.
- *Adjust-A-Link* rigging available for additional flexibility.







Rated Capacity (tons)	Part Number*	Spread (ft.)	Bail Dimensions (in.)			Hook Opening (H)	Headroom @45° (in.)	Weight (lbs.)	
			Oblong Diameter (A)	Oblong Opening Width (B)	Oblong Opening Height (C)			Beam & Hook	Chain Top Rigging
2	FSB4X4	4	0.63	3	6	0.91	36	45	12
	FSB4X6	6					48	60	15
	FSB4X8	8					61	82	20
	FSB4X10	10					74	95	25
	FSB4X12	12					86	115	30
	FSB4X16	16					111	225	40
	FSB4X20	20					139	408	50
	FSB4X24	24					164	445	60
5	FSB10X4	4	1	3.5	7	1.36	39	62	25
	FSB10X6	6					51	78	32
	FSB10X8	8					64	100	39
	FSB10X10	10					77	117	46
	FSB10X12	12					87	168	53
	FSB10X16	16					116	305	67
	FSB10X20	20					141	435	81
	FSB10X24	24					166	661	95
10	FSB20X4	4	1.25	4.38	8.75	1.60	43	100	40
	FSB20X6	6					56	122	52
	FSB20X8	8					67	156	64
	FSB20X10	10					81	180	76
	FSB20X12	12					90	240	88
	FSB20X16	16					119	380	112
	FSB20X20	20					145	532	136
	FSB20X24	24					171	915	160

* Add W to the part number for wire rope rigging; add A to the part number for *Adjust-A-Link* rigging.

ADJUSTABLE SPREADER BEAM (ASB32)

Features


- Great versatility and stability where headroom is not limited.
- Chain rigging standard.
- Wire rope rigging available.
- Telescoping spread adjusts in 1-inch increments.



Rated Capacity (tons)	Part Number*	Spread (ft.)	Bail Dimensions (in.)			Hook Opening (H)	Headroom Min. / Max. (in.)	Weight (lbs.)	
			Oblong Diameter (A)	Oblong Opening Width (B)	Oblong Opening Height (C)			Beam & Hook	Chain Top Rigging
2	ASB4X4-6	4 to 6	0.63	3	6	0.91	50 / 60	70	15
	ASB4X6-10	6 to 10					76 / 92	85	25
	ASB4X8-14	8 to 14					101 / 119	175	35
	ASB4X12-20	12 to 20					139 / 174	245	50
5	ASB10X4-6	4 to 6	1	3.5	7	1.36	58 / 67	105	32
	ASB10X6-10	6 to 10					83 / 100	160	46
	ASB10X8-14	8 to 14					107 / 132	205	60
	ASB10X12-20	12 to 20					145 / 181	670	81
10	ASB20X4-6	4 to 6	1.25	4.38	8.75	1.61	63 / 72	95	52
	ASB20X6-10	6 to 10					78 / 117	175	76
	ASB20X8-14	8 to 14					113 / 139	460	100
	ASB20X12-20	12 to 20					151 / 171	680	136
15	ASB30X4-6	4 to 6	1.50	5.25	10.50	2.08	67 / 76	165	75
	ASB30X6-10	6 to 10					91 / 109	365	109
	ASB30X8-14	8 to 14					117 / 142	478	143
	ASB30X12-20	12 to 20					154 / 189	700	194

* Add W to part number for wire rope rigging.


DIXON COIL HOOK WITH PIVOTING WEDGE (DCH80)




Features

- For easy upending of coils from horizontal to vertical.
- Pivoting wedge great for lifting stacked coils.
- Wedge also acts as a coil retainer.
- Great for use with small, lightweight coils.
- Good for limited overhead clearance.
- Standard handle for easier coil positioning.

Rated Capacity (tons)	Part Number	Max. Coil Width (in.)	Lift Arm Length (in.)	Lift Arm Height (in.)	Throat Opening Height (in.)	Bail Dimensions (in.)				Headroom	Weight (lbs.)
						Height	Opening Width	Opening Height	Thickness		
1/2	DCH1X6	8	8	2.25	14.5	0.75	2	3.25	0.5	18.6	13
1/2	DCH1X12	12	12	2.25	14.5	0.75	2	3.25	0.5	18.6	14
1	DCH2X8	8	8	2.25	17.5	0.81	2	3.25	0.5	21.6	15
2	DCH4X10	16	16	3.25	19.5	1	2.63	4	0.75	24.5	41
3-1/2	DCH7X12	12	12	3.25	21.5	1.19	3.63	5.5	1	28.2	57




HEAVY DUTY COIL HOOK (HDCH82)



Features

- Designed for heavy duty applications.
- High tensile alloy steel plate reduces physical size and weight.
- Counter balanced to hang level when empty.
- Inside radius on hooks to avoid coil edge contact.
- Guide handles for ease of hook positioning.
- Handles a wide range of coil widths.
- Available with optional padding for additional coil protection.



Rated Capacity (tons)	Part Number	Coil Width Min. / Max. (in.)	Lift Arm Dimensions (in.)			Throat Opening Height (in.)	Bail Dimensions (in.)				Headroom (in.)	Weight (lbs.)
			Length	Width	Height		Height	Opening Width	Opening Height	Thickness		
5	HDCH10X36	24 / 36	30	4	6.25	24	1.50	4	7	1.25	38.00	500
	HDCH10X48	30 / 48	39	4	6.25	24	1.50	4	7	1.25	38.00	730
	HDCH10X60	36 / 60	48	4	7.00	24	1.50	4	7	1.25	38.80	885
7-1/2	HDCH15X36	24 / 36	30	4	6.50	24	1.50	4	7	1.50	38.30	725
	HDCH15X48	30 / 48	39	4	7.25	24	1.50	4	7	1.50	39.00	875
	HDCH15X60	36 / 60	48	4	8.00	24	1.50	4	7	1.50	42.50	1060
10	HDCH20X48	30 / 48	39	4	8.25	24	2.00	5	9	1.75	42.50	1060
	HDCH20X60	36 / 60	48	4	8.25	24	2.00	5	9	1.75	43.30	1425
	HDCH20X72	42 / 72	57	4	9.00	24	2.00	5	9	1.75	49.30	1670
15	HDCH30X48	30 / 48	39	4	9.00	30	2.00	5	9	1.75	49.30	1615
	HDCH30X60	36 / 60	48	4	10.00	30	2.00	5	9	1.75	50.30	1925
	HDCH30X72	42 / 72	57	4	10.75	30	2.00	5	9	1.75	51.00	2220
20	HDCH40X60	36 / 60	48	4	10.50	30	2.25	6	12	2.0	54.00	2520
	HDCH40X72	42 / 72	57	4	11.50	30	2.25	6	12	2.0	55.00	2950




GIRDER CLAMPS (Use for Vertical Lifting Only)

Features

- Efficiently handles wide flange beam sections and plate girders.
- Design ensures positive grip and minimum maintenance.
- Thread screw spindles allow for quick clamping and unclamping.




Part Number	Rated Capacity (tons)	Dimensions (in.)								
		Flange Width		Max. Flange Thickness	A	B	C	D Min. - Max.	E Min. - Max.	Weight (lbs.)
		Min.	Max.							
GC15	15	6	24	3	14.81	3.90	1.60	23 - 44	15.7 - 23.4	234
GC20	20	6	24	3	14.81	5.00	2.10	23 - 44	18.3 - 25.9	291
GC25	25	6	24	3	14.81	5.00	2.10	23 - 44	18.3 - 25.9	342



For lifting and positioning structural beams.

Can be used in pairs in conjunction with a spreader beam for additional stability.







BEAM GRAB (F)

For Vertical Lifting Only (Not Suspension)

Features

- Heavy-duty design for lifting wide flange beams and plate girders.
- Recessed base accepts studs in beam surface.
- Eliminates need for slings, chokers and spreader bars.

Rated Capacity (tons)	Part Number	Unit Height H (in.)	Flange Width W (in.)		Flange Thickness T (in.)		Weight (lbs.)
			Min.	Max.	Min.	Max.	
5	F5	22.7	4	4	0.25	0.25	68
			5	5	0.25	0.38	
			6	10	0.25	1.00	
15	F15	30.1	7	7	0.50	0.75	182
			8	8	0.50	1.00	
			9	10	0.50	1.25	
			11	17	0.25	2.00	
25	F25	44.8	16	17	1.25	3.00	541
			18	24	1.00	3.00	
35	F35	52.9	16	18	2.25	4.00	841
			20	22	2.00	4.00	
			24	26	1.75	4.00	
			28	36	1.00	4.00	




Operation:

1. Lower grab onto beam.
2. Lift arms, if necessary, to slide under beam flange.
3. As beam is lifted, pressure forces arms together to secure beam.
4. The heavier the beam, the greater the clamping force.

PIPE GRAB (C OR S)


(For Cast Iron or Steel Pipe only)



Features

- Automatically clamps to pipe when lowered onto it.
- Movable outriggers stabilize the pipe during lift.
- No blocking required.
- Quick and efficient handling of properly balanced pipe.

Rated Capacity (lbs.)	Cast Iron		Steel		Height H (in.)	Width W (in.)	Depth D (in.)	Shackle Dimensions (in.) Dia. • B • C	Weight (lbs.)
	Part Number	Pipe OD (in.)	Part Number	Pipe OD (in.)					
450	C3	4.00	S3	3.50	10	5	6	0.38 • 1.03 • 1.44	7
600	C4	4.80	S4	4.50	14	8	7	0.44 • 1.16 • 1.69	9
1000	C6	6.90	S6	6.63	17	11	11	0.50 • 1.31 • 1.88	15
1400	C8	9.05	S8	8.63	22	13	14	0.50 • 1.31 • 1.88	25



Operation:

1. Lower grab onto approximate center of pipe. Grab will open and seat on pipe.
2. Lift slowly to check for pipe balance. Never exceed a 15° angle.
3. If angle exceeds 15°, lower pipe and reposition grab.

PIPE TONGS (PTL)

For Vertical Lifting Only (not Suspension)



Adjustable




Fixed


Features

- Pipe Tongs are made to handle pipes, round bars, castings, etc.
- Tongs are provided with bare steel curved gripping arms.
- Optional replaceable urethane pads available to protect smooth or polished surfaces.
- May be used in pairs with a lifting beam for added stability.
- Adjustable Pipe Tongs are proof-tested to 125% capacity with certificates supplied at no additional charge.

FIXED DIAMETER						
Rated Capacity (lbs.)	Part Number	Dia. (in.)	Headroom Minimum (in.)	A (in.)	B (in.)	Weight (lbs.)
1000	PTLF5	5	15.50	0.50	1.31	17
2000	PTLF8	8	23.50	0.50	1.31	25



ADJUSTABLE DIAMETER									
Rated Capacity (lbs.)	Part Number	Bare Steel Range Min. / Max. (in.)	Urethane Pad Range Min. / Max. (in.)	Headroom Range Min. / Max. (in.)	Pad Width (in.)	Bail Height (in.)	Bail Opening Width (in.)	Bail Opening Height (in.)	Weight (lbs.)
1000	PTLA4	2.50 / 4.00	1.75 - 3.25	13 - 15	2.25	0.63	1.69	1.69	10
2000	PTLA8	4.00 / 7.00	3.25 - 6.25	21 - 24	5.00	0.63	1.69	1.69	25
2000	PTLA12	7.00 / 12.00	6.25 - 11.25	34 - 38	6.00	0.75	2	2	55
2000	PTLA15	10.00 / 15.00	9.25 - 14.25	25 - 35	6.00	0.75	2.25	3.25	120



WARNING

Decreasing the load by bumping or substantial imbalance can, under certain circumstances, loosen the grip. Do not use in diameters other than those specified on nameplate.

CONCRETE MANHOLE HOUSING LIFTER (MHL)

Features






- Designed for 4" - 6" concrete wall thickness.
- Will not damage concrete seat.
- Legs can be quickly positioned to balance load.
- 2-leg and 3-leg models available.
- Conforms to ASME B30.9 & B30.20.



Note: Constant tension is required to maintain positive load contact.



Rated Capacity (lbs.)	Part Number	Description	Max. Dia.	Weight (lbs.)
10,000	MHL5	2-Leg Model (42" each leg)	92.5	131
15,000	MHL7-1/2	3-Leg Model (2 legs @ 42", 1 leg @ 72" with chain shortener)	101	181
5,000	MHLC	Clamp Only	—	45



MANHOLE SLEEVE LIFTER (MCL)

General Information	Web Slings	Round Slings	Slings Protection	Wire Rope	Chain Slings	Rigging Hardware	Mesh Slings	Load Huggers	Tow Products	Lift-All Hoists	Hoist Rings	Plate Clamps	Lifting Devices
---------------------	------------	--------------	-------------------	-----------	--------------	------------------	-------------	--------------	--------------	-----------------	-------------	--------------	-----------------




2-Leg Lifter



Features

- Easy to attach and release from sleeve.
- The quick and easy way to place cast manhole sleeves.
- 2-leg or 3-leg models available.






Note: Flange diameter range is 12" - 30"




3-Leg Lifter



Rated Capacity (lbs.)	Part Number	Description	Weight (lbs.)
1,000	MCL1/2	2-Leg Model	24
1,500	MCL3/4	3-Leg Model (2-legs @ 18", 1-leg @ 30" with chain shortener)	26




BARRIER LIFTING GRAB (BRG74)



Features


- Compact and rugged design.
- Grabs concrete barriers from 6"–12" nominal width at the top of barrier.
- Stainless steel auto-latch designed to ensure proper alignment.
- Locating assembly orients tong on barrier without operator intervention and will pivot when grab is set on the ground.
- Gripping pads pivot to conform with the load.
- Replaceable polyurethane pads protect barrier.
- Alloy steel dog point pads bite into painted barrier surfaces (typical in coastal areas).
- Centering guide cut out on grab shoe helps to properly center tong over barrier for a level lift.
- Extended handles on each side keep operator away from load and can be adjusted as needed.
- Lifting eye allows for easy hook attachment, self-centers rigging, and will accommodate a fork.

Rated Capacity (lbs.)	Part Number	Weight (lbs.)
With Polyurethane Lifting Pads		
8,500	BRG74-4.25	602
14,500	BRG74-7.25	652
With Steel Dog Point Lifting Pads		
8,500	BRG74-4.25DP	602
14,500	BRG74-7.25DP	652




OPERATION


Place tong on barrier, lower crane completely to disengage the auto-latch.



Lift and position barrier in desired location.




Lower crane (line must go slack to engage auto-latch), lift tong off barrier and repeat!



TELESCOPING FORKLIFT BOOMS (TFLB)


Features

- Telescoping boom for versatility.
- T-Pin locks boom into position.
- Handle on end for easy extension of boom.
- Swivel hooks with latch standard.
- Restraining chain with grab hook standard.
- 12-ft. maximum horizontal reach.



Part Number	Dimensions (in.)					Maximum Capacity at Hook Position (lbs.)							Weight (lbs.)
	Fork Opening Height	Fork Opening Width	Fork Outside Width	Headroom	Hook Opening	3' - 6'	7'	8'	9'	10'	11'	12'	
TFLB30	2.5	7	22	18	1	3,000	3,000	2,600	2,200	1,900	1,600	1,500	490
TFLB40	2.5	7	22	18	1.09	4,000	3,200	2,600	2,200	1,900	1,600	1,500	490
TFLB60	2.5	7	22	18	1.36	6,000	5,000	4,200	3,500	3,000	2,700	2,500	565
TFLB80	2.5	7	22	18	1.61	8,000	7,000	5,700	4,800	4,100	3,600	3,100	750

PIVOTING FORKLIFT BOOMS (PFLB)



Features


- Vertical adjustability in five increments up to a maximum of 40°.
- Telescoping boom for versatility.
- T-Pin locks boom into position.
- Handle on end for easy extension of boom.
- Swivel hooks with latch are standard.
- Restraining chain with grab hook standard reach.
- Vertical pivoting boom to 6' 4" height.

Part Number	Dimensions (in.)					Maximum Capacity at Hook Position (lbs.)							Weight (lbs.)
	Fork Opening Height	Fork Opening Width	Fork Outside Width	Headroom	Hook Opening	3' - 6'	7'	8'	9'	10'	11'	12'	
PFLB30	2.5	7	22.5	30	1	3,000	3,000	2,600	2,200	1,900	1,600	1,500	565
PFLB40	2.5	7	22.5	30	1.09	4,000	3,200	2,600	2,200	1,900	1,600	1,500	565
PFLB60	2.5	7	22.5	30	1.36	6,000	5,000	4,200	3,500	3,000	2,700	2,500	680
PFLB80	2.5	7	22.5	30	1.61	8,000	7,000	5,700	4,800	4,100	3,600	3,100	870

FIXED HEIGHT STEEL (H90)

Features


- Balanced design allows for easy rolling, even under load.
- Simple bolt together construction.
- Includes four steel swivel casters.
- Easy set-up and maintenance.
- Adjustable span from 10' to 16'.



Rated Capacity	Height Under Beam H	Nominal Span (ft.)	Inside Span A	Overall Length B	Support Width C	Beam Height D (in.)	Flange Width E (in.)	Caster Diameter (in.)	Weight (lbs.)	Part Number
1-Ton	10'	10	10'-4"	11'-6"	5'-6"	8	5.25	6	825	511-2000-10-10
		12	12'-4"	13'-6"	5'-6"	8	5.25	6	930	511-2000-12-10
		14	14'-4"	15'-6"	5'-6"	8	5.25	6	967	511-2000-14-10
		16	16'-4"	17'-6"	5'-6"	8	5.25	6	1136	511-2000-16-10
	12	10	10'-4"	11'-6"	6'-6"	8	5.25	6	913	511-2000-10-12
		12	12'-4"	13'-6"	6'-6"	8	5.25	6	1018	511-2000-12-12
		14	14'-4"	15'-6"	6'-6"	8	5.25	6	1055	511-2000-14-12
		16	16'-4"	17'-6"	6'-6"	8	5.25	6	1224	511-2000-16-12
	14'	10	10'-4"	11'-6"	7'-6"	8	5.25	6	977	511-2000-10-14
		12	12'-4"	13'-6"	7'-6"	8	5.25	6	1082	511-2000-12-14
		14	14'-4"	15'-6"	7'-6"	8	5.25	6	1119	511-2000-14-14
		16	16'-4"	17'-6"	7'-6"	8	5.25	6	1288	511-2000-16-14
	16'	10	10'-4"	11'-6"	7'-6"	8	5.25	6	1081	511-2000-10-16
		12	12'-4"	13'-6"	7'-6"	8	5.25	6	1186	511-2000-12-16
		14	14'-4"	15'-6"	7'-6"	8	5.25	6	1223	511-2000-14-16
		16	16'-4"	17'-6"	7'-6"	8	5.25	6	1392	511-2000-16-16

FIXED HEIGHT STEEL (H90)


(continued)



Rated Capacity	Height Under Beam H	Nominal Span (ft.)	Inside Span A	Overall Length B	Support Width C	Beam Height D (in.)	Flange Width E (in.)	Caster Diameter (in.)	Weight (lbs.)	Part Number
2-Ton	10'	10	10'-4"	11'-6"	5'-6"	8	5.25	8	949	511-4000-10-10
		12	12'-4"	13'-6"	5'-6"	8	5.25	8	986	511-4000-12-10
		14	14'-4"	15'-6"	5'-6"	10	5.75	8	1131	511-4000-14-10
		16	16'-4"	17'-6"	5'-6"	10	5.75	8	1182	511-4000-16-10
	12'	10	10'-4"	11'-6"	6'-6"	8	5.25	8	1041	511-4000-10-12
		12	12'-4"	13'-6"	6'-6"	8	5.25	8	1078	511-4000-12-12
		14	14'-4"	15'-6"	6'-6"	10	5.75	8	1223	511-4000-14-12
		16	16'-4"	17'-6"	6'-6"	10	5.75	8	1274	511-4000-16-12
	14'	10	10'-4"	11'-6"	7'-6"	8	5.25	8	1101	511-4000-10-14
		12	12'-4"	13'-6"	7'-6"	8	5.25	8	1138	511-4000-12-14
		14	14'-4"	15'-6"	7'-6"	10	5.75	8	1283	511-4000-14-14
		16	16'-4"	17'-6"	7'-6"	10	5.75	8	1334	511-4000-16-14
	16'	10	10'-4"	11'-6"	7'-6"	8	5.25	8	1205	511-4000-10-16
		12	12'-4"	13'-6"	7'-6"	8	5.25	8	1242	511-4000-12-16
		14	14'-4"	15'-6"	7'-6"	10	5.75	8	1387	511-4000-14-16
		16	16'-4"	17'-6"	7'-6"	10	5.75	8	1438	511-4000-16-16
3-Ton	10'	10	9'-3"	11'-6"	5'-6"	10	6.50	8	1107	511-6000-10-10
		12	11'-3"	13'-6"	5'-6"	10	6.50	8	1157	511-6000-12-10
		14	13'-3"	15'-6"	5'-6"	10	6.50	8	1208	511-6000-14-10
		16	15'-3"	17'-6"	5'-6"	12	6.50	8	1427	511-6000-16-10
	12'	10	9'-3"	11'-6"	6'-6"	10	6.50	8	1229	511-6000-10-12
		12	11'-3"	13'-6"	6'-6"	10	6.50	8	1279	511-6000-12-12
		14	13'-3"	15'-6"	6'-6"	10	6.50	8	1330	511-6000-14-12
		16	15'-3"	17'-6"	6'-6"	12	6.50	8	1529	511-6000-16-12
	14'	10	9'-3"	11'-6"	7'-6"	10	6.50	8	1350	511-6000-10-14
		12	11'-3"	13'-6"	7'-6"	10	6.50	8	1400	511-6000-12-14
		14	13'-3"	15'-6"	7'-6"	10	6.50	8	1451	511-6000-14-14
		16	15'-3"	17'-6"	7'-6"	12	6.50	8	1670	511-6000-16-14
	16'	10	9'-3"	11'-6"	7'-6"	10	6.50	8	1473	511-6000-10-16
		12	11'-3"	13'-6"	7'-6"	10	6.50	8	1523	511-6000-12-16
		14	13'-3"	15'-6"	7'-6"	10	6.50	8	1574	511-6000-14-16
		16	15'-3"	17'-6"	7'-6"	12	6.50	8	1793	511-6000-16-16


FIXED HEIGHT STEEL (H90)

(continued)



Rated Capacity	Height Under Beam H	Nominal Span (ft.)	Inside Span A	Overall Length B	Support Width C	Beam Height D (in.)	Flange Width E (in.)	Caster Diameter (in.)	Weight (lbs.)	Part Number
4-Ton	10'	10	9'-3"	11'-6"	5'-6"	16	7.00	8	1217	511-8000-10-10
		12	11'-3"	13'-6"	5'-6"	16	7.00	8	1877	511-8000-12-10
		14	13'-3"	15'-6"	5'-6"	18	7.50	8	1357	511-8000-14-10
		16	15'-3"	17'-6"	5'-6"	18	7.50	8	1812	511-8000-16-10
	12'	10	9'-3"	11'-6"	6'-6"	16	7.00	8	1339	511-8000-10-12
		12	11'-3"	13'-6"	6'-6"	16	7.00	8	1409	511-8000-12-12
		14	13'-3"	15'-6"	6'-6"	18	7.50	8	1479	511-8000-14-12
		16	15'-3"	17'-6"	6'-6"	18	7.50	8	1934	511-8000-16-12
	14'	10	9'-3"	11'-6"	7'-6"	16	7.00	8	1460	511-8000-10-14
		12	11'-3"	13'-6"	7'-6"	16	7.00	8	1530	511-8000-12-14
		14	13'-3"	15'-6"	7'-6"	18	7.50	8	1600	511-8000-14-14
		16	15'-3"	17'-6"	7'-6"	18	7.50	8	2055	511-8000-16-14
	16'	10	9'-3"	11'-6"	7'-6"	16	7.00	8	1583	511-8000-10-16
		12	11'-3"	13'-6"	7'-6"	16	7.00	8	1653	511-8000-12-16
		14	13'-3"	15'-6"	7'-6"	18	7.50	8	1723	511-8000-14-16
		16	15'-3"	17'-6"	7'-6"	18	7.50	8	2178	511-8000-16-16
5-Ton	10'	10	9'-3"	11'-6"	5'-6"	16	7.00	8	1397	511-10000-10-10
		12	11'-3"	13'-6"	5'-6"	16	7.00	8	1467	511-10000-12-10
		14	13'-3"	15'-6"	5'-6"	18	7.50	8	1537	511-10000-14-10
		16	15'-3"	17'-6"	5'-6"	18	7.50	8	1992	511-10000-16-10
	12'	10	9'-3"	11'-6"	6'-6"	16	7.00	8	1519	511-10000-10-12
		12	11'-3"	13'-6"	6'-6"	16	7.00	8	1589	511-10000-12-12
		14	13'-3"	15'-6"	6'-6"	18	7.50	8	1659	511-10000-14-12
		16	15'-3"	17'-6"	6'-6"	18	7.50	8	2114	511-10000-16-12
	14'	10	9'-3"	11'-6"	7'-6"	16	7.00	8	1640	511-10000-10-14
		12	11'-3"	13'-6"	7'-6"	16	7.00	8	1710	511-10000-12-14
		14	13'-3"	15'-6"	7'-6"	18	7.50	8	1780	511-10000-14-14
		16	15'-3"	17'-6"	7'-6"	18	7.50	8	2235	511-10000-16-14
	16'	10	9'-3"	11'-6"	7'-6"	16	7.00	8	1763	511-10000-10-16
		12	11'-3"	13'-6"	7'-6"	16	7.00	8	1833	511-10000-12-16
		14	13'-3"	15'-6"	7'-6"	18	7.50	8	1903	511-10000-14-16
		16	15'-3"	17'-6"	7'-6"	18	7.50	8	2358	511-10000-16-16

ADJUSTABLE HEIGHT STEEL (K90)



Features

- Balanced design allows for easy rolling, even under load.
- Simple bolt together construction.
- Includes four steel swivel casters.
- Easy set-up and maintenance.
- Maximum height can be reduced in one foot increments.
- Adjustable span standard.

Rated Capacity	Max. Height Under Beam H	Nominal Span (ft.)	Inside Span A	Overall Length B	Support Width C	Beam Height D (in.)	Flange Width E (in.)	Caster Diameter (in.)	Min. Height Under Beam H (ft.)	Weight (lbs.)	Part Number
1-Ton	8'	10	10'-5"	11'-6"	5'-0"	8	5.25	6	5'-0"	625	512-2000-10-8
		12	12'-5"	13'-6"	5'-0"	8	5.25	6	5'-0"	725	512-2000-12-8
		14	14'-5"	15'-6"	5'-0"	8	5.25	6	5'-0"	750	512-2000-14-8
		16	16'-5"	17'-6"	5'-0"	8	5.25	6	5'-0"	925	512-2000-16-8
	10'	10	10'-5"	11'-6"	5'-6"	8	5.25	6	7'-0"	650	512-2000-10-10
		12	12'-5"	13'-6"	5'-6"	8	5.25	6	7'-0"	750	512-2000-12-10
		14	14'-5"	15'-6"	5'-6"	8	5.25	6	7'-0"	800	512-2000-14-10
		16	16'-5"	17'-6"	5'-6"	8	5.25	6	7'-0"	950	512-2000-16-10
	12'	10	10'-5"	11'-6"	6'-6"	8	5.25	6	8'-0"	750	512-2000-10-12
		12	12'-5"	13'-6"	6'-6"	8	5.25	6	8'-0"	850	512-2000-12-12
		14	14'-5"	15'-6"	6'-6"	8	5.25	6	8'-0"	900	512-2000-14-12
		16	16'-5"	17'-6"	6'-6"	8	5.25	6	8'-0"	1050	512-2000-16-12
	14'	10	10'-5"	11'-6"	7'-6"	8	5.25	6	10'-0"	800	512-2000-10-14
		12	12'-5"	13'-6"	7'-6"	8	5.25	6	10'-0"	900	512-2000-12-14
		14	14'-5"	15'-6"	7'-6"	8	5.25	6	10'-0"	950	512-2000-14-14
		16	16'-5"	17'-6"	7'-6"	8	5.25	6	10'-0"	1100	512-2000-16-14
	16'	10	10'-5"	11'-6"	7'-6"	8	5.25	6	12'-0"	850	512-2000-10-16
		12	12'-5"	13'-6"	7'-6"	8	5.25	6	12'-0"	950	512-2000-12-16
		14	14'-5"	15'-6"	7'-6"	8	5.25	6	12'-0"	1000	512-2000-14-16
		16	16'-5"	17'-6"	7'-6"	8	5.25	6	12'-0"	1150	512-2000-16-16


ADJUSTABLE HEIGHT STEEL (K90)

(continued)



Rated Capacity	Max. Height Under Beam H	Nominal Span (ft.)	Inside Span A	Overall Length B	Support Width C	Beam Height D (in.)	Flange Width E (in.)	Caster Diameter (in.)	Min. Height Under Beam H (ft.)	Weight (lbs.)	Part Number
2-Ton	8'	10	10'-5"	11'-6"	5'-0"	8	5.25	8	5'-0"	750	512-4000-10-8
		12	12'-5"	13'-6"	5'-0"	8	5.25	8	5'-0"	800	512-4000-12-8
		14	14'-5"	15'-6"	5'-0"	10	5.75	8	5'-0"	925	512-4000-14-8
		16	16'-5"	17'-6"	5'-0"	10	5.75	8	5'-0"	975	512-4000-16-8
	10'	10	10'-5"	11'-6"	5'-6"	8	5.25	8	7'-0"	775	512-4000-10-10
		12	12'-5"	13'-6"	5'-6"	8	5.25	8	7'-0"	825	512-4000-12-10
		14	14'-5"	15'-6"	5'-6"	10	5.75	8	7'-0"	975	512-4000-14-10
		16	16'-5"	17'-6"	5'-6"	10	5.75	8	7'-0"	1025	512-4000-16-10
	12'	10	10'-5"	11'-6"	6'-6"	8	5.25	8	8'-0"	875	512-4000-10-12
		12	12'-5"	13'-6"	6'-6"	8	5.25	8	8'-0"	900	512-4000-12-12
		14	14'-5"	15'-6"	6'-6"	10	5.75	8	8'-0"	1050	512-4000-14-12
		16	16'-5"	17'-6"	6'-6"	10	5.75	8	8'-0"	1100	512-4000-16-12
	14'	10	10'-5"	11'-6"	7'-6"	8	5.25	8	10'-0"	950	512-4000-10-14
		12	12'-5"	13'-6"	7'-6"	8	5.25	8	10'-0"	975	512-4000-12-14
		14	14'-5"	15'-6"	7'-6"	10	5.75	8	10'-0"	1125	512-4000-14-14
		16	16'-5"	17'-6"	7'-6"	10	5.75	8	10'-0"	1175	512-4000-16-14
	16'	10	10'-5"	11'-6"	7'-6"	8	5.25	8	12'-0"	1000	512-4000-10-16
		12	12'-5"	13'-6"	7'-6"	8	5.25	8	12'-0"	1025	512-4000-12-16
		14	14'-5"	15'-6"	7'-6"	10	5.75	8	12'-0"	1175	512-4000-14-16
		16	16'-5"	17'-6"	7'-6"	10	5.75	8	12'-0"	1225	512-4000-16-16


ADJUSTABLE HEIGHT STEEL (K90) (continued)



Rated Capacity	Max. Height Under Beam H	Nominal Span (ft.)	Inside Span A	Overall Length B	Support Width C	Beam Height D (in.)	Flange Width E (in.)	Caster Diameter (in.)	Min. Height Under Beam H (ft.)	Weight (lbs.)	Part Number
3-Ton	8'	10	9'-5"	11'-6"	5'-0"	12	6.50	8	5'-0"	1100	512-6000-10-8
		12	11'-5"	13'-6"	5'-0"	12	6.50	8	5'-0"	1175	512-6000-12-8
		14	13'-5"	15'-6"	5'-0"	12	6.50	8	5'-0"	1225	512-6000-14-8
		16	15'-5"	17'-6"	5'-0"	12	6.50	8	5'-0"	1375	512-6000-16-8
	10'	10	9'-5"	11'-6"	5'-6"	12	6.50	8	7'-0"	1175	512-6000-10-10
		12	11'-5"	13'-6"	5'-6"	12	6.50	8	7'-0"	1200	512-6000-12-10
		14	13'-5"	15'-6"	5'-6"	12	6.50	8	7'-0"	1275	512-6000-14-10
		16	15'-5"	17'-6"	5'-6"	12	6.50	8	7'-0"	1425	512-6000-16-10
	12'	10	9'-5"	11'-6"	6'-6"	12	6.50	8	8'-0"	1300	512-6000-10-12
		12	11'-5"	13'-6"	6'-6"	12	6.50	8	8'-0"	1375	512-6000-12-12
		14	13'-5"	15'-6"	6'-6"	12	6.50	8	8'-0"	1400	512-6000-14-12
		16	15'-5"	17'-6"	6'-6"	12	6.50	8	8'-0"	1575	512-6000-16-12
	14'	10	9'-5"	11'-6"	7'-6"	12	6.50	8	10'-0"	1400	512-6000-10-14
		12	11'-5"	13'-6"	7'-6"	12	6.50	8	10'-0"	1475	512-6000-12-14
		14	13'-5"	15'-6"	7'-6"	12	6.50	8	10'-0"	1525	512-6000-14-14
		16	15'-5"	17'-6"	7'-6"	12	6.50	8	10'-0"	1675	512-6000-16-14
	16'	10	9'-5"	11'-6"	7'-6"	12	6.50	8	12'-0"	1500	512-6000-10-16
		12	11'-5"	13'-6"	7'-6"	12	6.50	8	12'-0"	1550	512-6000-12-16
		14	13'-5"	15'-6"	7'-6"	12	6.50	8	12'-0"	1600	512-6000-14-16
		16	15'-5"	17'-6"	7'-6"	12	6.50	8	12'-0"	1750	512-6000-16-16

ADJUSTABLE HEIGHT STEEL (K90)

(continued)



Rated Capacity	Max. Height Under Beam H	Nominal Span (ft.)	Inside Span A	Overall Length B	Support Width C	Beam Height D (in.)	Flange Width E (in.)	Caster Diameter (in.)	Min. Height Under Beam H (ft.)	Weight (lbs.)	Part Number
5-Ton	8'	10	9'-5"	11'-6"	5'-0"	16	7.00	8	6'-1"	1325	512-10000-10-8
		12	11'-5"	13'-6"	5'-0"	16	7.00	8	6'-1"	1375	512-10000-12-8
		14	13'-5"	15'-6"	5'-0"	18	7.50	8	6'-1"	1625	512-10000-14-8
		16	15'-5"	17'-6"	5'-0"	18	7.50	8	6'-1"	1700	512-10000-16-8
	10'	10	9'-5"	11'-6"	5'-6"	16	7.00	8	7'-1"	1375	512-10000-10-10
		12	11'-5"	13'-6"	5'-6"	16	7.00	8	7'-1"	1425	512-10000-12-10
		14	13'-5"	15'-6"	5'-6"	18	7.50	8	7'-1"	1675	512-10000-14-10
		16	15'-5"	17'-6"	5'-6"	18	7.50	8	7'-1"	1750	512-10000-16-10
	12'	10	9'-5"	11'-6"	6'-6"	16	7.00	8	8'-1"	1550	512-10000-10-12
		12	11'-5"	13'-6"	6'-6"	16	7.00	8	8'-1"	1600	512-10000-12-12
		14	13'-5"	15'-6"	6'-6"	18	7.50	8	8'-1"	1825	512-10000-14-12
		16	15'-5"	17'-6"	6'-6"	18	7.50	8	8'-1"	1925	512-10000-16-12
	14'	10	9'-5"	11'-6"	7'-6"	16	7.00	8	9'-1"	1650	512-10000-10-14
		12	11'-5"	13'-6"	7'-6"	16	7.00	8	9'-1"	1725	512-10000-12-14
		14	13'-5"	15'-6"	7'-6"	18	7.50	8	9'-1"	1950	512-10000-14-14
		16	15'-5"	17'-6"	7'-6"	18	7.50	8	9'-1"	2050	512-10000-16-14
	16'	10	9'-5"	11'-6"	7'-6"	16	7.00	8	10'-1"	1725	512-10000-10-16
		12	11'-5"	13'-6"	7'-6"	16	7.00	8	10'-1"	1800	512-10000-12-16
		14	13'-5"	15'-6"	7'-6"	18	7.50	8	10'-1"	2025	512-10000-14-16
		16	15'-5"	17'-6"	7'-6"	18	7.50	8	10'-1"	2125	512-10000-16-16

ADJUSTABLE ALUMINUM (KA90)




Features

- Lightweight aluminum construction.
- Balanced design allows for easy rolling under load.
- Simple bolt together construction.
- Includes four poly coated swivel casters.
- Easy setup and maintenance.
- Height adjustable in 6" increments.

Rated Capacity	Min./Max. Height Under Beam H	Nominal Span (ft.)	Inside Span A	Overall Length B	Support Width C	Beam Height D (in.)	Flange Width E (in.)	Caster Diameter (in.)	Weight (lbs.)	Part Number
1/2-Ton	7' - 6" min. 10' - 0" max.	8	7'-3"	8'-9"	4'-6"	5	3.00	6	125	582-1000-8-10
		10	9'-3"	10'-9"	4'-6"	6	3.38	6	145	582-1000-10-10
		12	11'-3"	12'-9"	4'-6"	8	4.00	6	175	582-1000-12-10
		15	14'-3"	15'-9"	4'-6"	8	4.00	6	205	582-1000-15-10
	9' - 6" min. 12' - 0" max.	8	7'-3"	8'-9"	5'-0"	5	3.00	6	140	582-1000-8-12
		10	9'-3"	10'-9"	5'-0"	6	3.38	6	160	582-1000-10-12
		12	11'-3"	12'-9"	5'-0"	8	4.00	6	190	582-1000-12-12
		15	14'-3"	15'-9"	5'-0"	8	4.00	6	220	582-1000-15-12
1-Ton	7' - 6" min. 10' - 0" max.	8	7'-3"	8'-9"	4'-6"	6	3.38	6	165	582-2000-8-10
		10	9'-3"	10'-9"	4'-6"	8	4.00	6	195	582-2000-10-10
		12	11'-3"	12'-9"	4'-6"	8	4.00	6	215	582-2000-12-10
		15	14'-3"	15'-9"	4'-6"	10	4.63	6	260	582-2000-15-10
	9' - 6" min. 12' - 0" max.	8	7'-3"	8'-9"	5'-0"	6	3.38	6	180	582-2000-8-12
		10	9'-3"	10'-9"	5'-0"	8	4.00	6	210	582-2000-10-12
		12	11'-3"	12'-9"	5'-0"	8	4.00	6	245	582-2000-12-12
		15	14'-3"	15'-9"	5'-0"	10	4.63	6	300	582-2000-15-12
2-Ton	7' - 6" min. 10' - 0" max.	8	7'-3"	8'-9"	4'-6"	8	4.00	8	250	582-4000-8-10
		10	9'-3"	10'-9"	4'-6"	10	4.63	8	290	582-4000-10-10
		12	11'-3"	12'-9"	4'-6"	12	5.00	8	340	582-4000-12-10
		15	14'-3"	15'-9"	4'-6"	12	5.00	8	375	582-4000-15-10
	9' - 6" min. 12' - 0" max.	8	7'-3"	8'-9"	5'-0"	8	4.00	8	280	582-4000-8-12
		10	9'-3"	10'-9"	5'-0"	10	4.63	8	320	582-4000-10-12
		12	11'-3"	12'-9"	5'-0"	12	5.00	8	365	582-4000-12-12
		15	14'-3"	15'-9"	5'-0"	12	5.00	8	400	582-4000-15-12
3-Ton	7' - 6" min. 10' - 0" max.	8	7'-3"	8'-9"	5'-0"	12	5.00	8	390	582-6000-8-10
		10	9'-3"	10'-9"	5'-0"	12	5.00	8	395	582-6000-10-10
		12	11'-3"	12'-9"	5'-0"	12	5.00	8	450	582-6000-12-10
		15	14'-3"	15'-9"	5'-0"	12	5.00	8	490	582-6000-15-10
	9' - 6" min. 12' - 0" max.	8	7'-3"	8'-9"	5'-0"	12	5.00	8	425	582-6000-8-12
		10	9'-3"	10'-9"	5'-0"	12	5.00	8	445	582-6000-10-12
		12	11'-3"	12'-9"	5'-0"	12	5.00	8	502	582-6000-12-12
		15	14'-3"	15'-9"	5'-0"	12	5.00	8	548	582-6000-15-12

A collection of blue line-art illustrations of various mechanical tools and equipment, including cranes, hoists, and lifting devices, arranged on a grid background. A yellow pencil is drawn diagonally across the center of the image.



BASIC INFORMATION

Lift-All Company can provide a unique engineered device for your production requirements. Our custom devices range from large capacity beams to small S-Hooks or J-Hooks.

Features and Benefits

- Specifically designed equipment for the ultimate in safety.
- All equipment conforms to highest engineering standards and meets or exceeds government and industry regulations (ASME B30.20).
- Helps eliminate employee fatigue - raises morale and quality of work.
- Productivity improves through efficiency when using properly designed lifting devices.
- Equipment can be designed to prevent costly load damage.
- Rugged materials and construction provide long useful life.

Inspection Criteria for Lifting Devices

Visually inspect lifting device and slings prior to each lift. Have competent person record inspection a minimum of once a year. Follow all warnings and care/use instructions supplied with the device. Check the following and correct before use:

- Structural deformation, cracks, excessive wear.
- Loose or missing guards, fasteners, covers, stops or name plates.
- Inoperable mechanisms including automatic hold or release devices.
- Loose bolts or fasteners.
- Cracked or worn gears, pulleys, sheaves, sprockets, bearings and chains.
- Excessive wear of friction pads, linkage or other mechanical parts.
- Excessive wear of hoist hooking points and load support clevises or pins.


Safe Operating Practices

- Use only per ASME B30.20.
- Check name plate to assure proper lifting capacity.
- Perform a test load a sufficient distance to assure that the load is supported properly by the lifter and then inspect lifter for defects and deformation.
- Instruct the operator in correct lifting practices including proper storage, load distribution, use of associated slings, temperature considerations, avoidance of obstructions, acceleration, side pulls and angle of lift. Read HELP section of this catalog.
- Never lift over people and never ride the load.
- For proper use of slings with lifting devices refer to ASME B30.9 and appropriate section of this catalog.

How to Order

1. Review and understand the HELP section in this catalog.
2. Copy appropriate drawing from the following pages or download from our website www.lift-all.com under **Products/Lifting Devices/Custom Lifting Devices**.
3. Enter the information and fax to 717-898-1215, or scan and email to: customerservice@lift-all.com. For assistance call us at 800-909-1964.
4. Our engineering drawing will be sent to you for approval and purchase order.

Spreader Beam



Required Information

Opening required for Overhead Hook:

A (Height) _____

B (Width) _____

C (Max.) _____

Capacity Required _____

Spread _____

Headroom _____


D (**Options**) _____

Is load center of gravity centered between other pick points? **Yes** ☐ **No** ☐

If no, specify location in reference to pick points (attach a diagram if necessary): _____

If adjustable beam required, list quantity and spread for any additional pairs of holes, pins and hooks.

Low Headroom lifting Beam



NOTE: Custom Engineered Products are Non-Returnable.

Quotation Needed By: _____
Date _____

Date _____ From _____
Person Requesting Quote _____

Distributor

Address

City _____ State _____ Zip _____

Phone _____ Email _____

Drawing Number:




Name and Phone Number

Purchase Order Number



Signature	Date
-----------	------

Custom Engineered Products are Non-Returnable

Custom Engineered Products are Non-Returnable

Alloy S-Hook		Alloy J-Hook		LiftAll [®] PRODUCTS FOR BETTER LIFTING		Required Information	
						S-HOOK Material Diameter _____ Rated Capacity _____ Chain Size: _____ A _____ B _____ C _____ D _____ R (Radius) _____	
						J-HOOK Style: Circle One A B C Tip: Flat-Tapered _____ Rated Capacity _____ Chain Size: _____ A _____ B _____ C _____ D _____ E _____ F _____ R (Tip Radius) _____ Special Instructions: _____	
Quotation Needed By: _____ Date _____		Drawing Number: _____					
Date _____ From _____ Person Requesting Quote		Name and Phone Number _____					
Distributor _____		Purchase Order Number _____					
Address _____		Signature _____				Date _____	
City _____ State _____ Zip _____							
Phone _____ Email _____							

Custom Engineered Products are Non-Returnable

STANDARD COIL LIFTER		STANDARD PALLET LIFTER	
 			
Required Information Style Requested _____ Capacity _____ Minimum Coil I.D. _____ Maximum Coil O.D. _____ Maximum Coil Width _____ Size of Overhead Hook (Cap.) _____ A _____ B _____ C (Minimum) _____ D (Minimum) _____ E _____ F (Options) _____ G _____ H (Options) _____ R (Options) _____ Back Stop Pad ☐ Yes ☐ No Special Instructions: _____			
Quotation Needed By: _____ Date _____		Drawing Number: _____	
Date _____ From _____ Person Requesting Quote		Name and Phone Number _____	
Distributor _____		Purchase Order Number _____	
Address _____		Signature _____	
City _____ State _____ Zip _____		Date _____	
Phone _____ Email _____		Custom Engineered Products are Non-Returnable	

Custom Engineered Products are Non-Returnable